ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 21st February 1937.

The attention of the public is hereby invited to the notification, dated 17th February 1937, calling for tenders for the work of providing sanitary installation in the New Railway Offices at Mysore, published in pages 270-272 of Part VI of the *Mysore Gazette*, dated 25th February 1937.

The last date of receiving tenders is fixed on 15th March 1937.

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 4th March 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 2nd April 1937, for maintenance work to Jalige Major tank Register No. 104 of Devanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for maintenance work to Jalige Major tank Register No. 104 of Devanhalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond after depositing an additional sum of Rs. 100 in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for the maintenance work to Jalige Major Tank Register No. 104 of Devanhalli Taluk.

No.	Details of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
				Rs. a. p.		
1	Cutting and removing jungle including roots	Grade	25	1 0 0		
2	Cutting grips on slopes of bund ..	„	27	2 0 0		
3	Earthwork to bund with the required load and lift and watering and tamping	C.yd.	6,194	0 4 0		
4	Turfing the slopes of bund sanding and watering till it is satisfactory	S.yd.	6,889	0 1 0		

N. SUBBA RAO,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 18th February 1937.

Attention of the public is drawn to Notification calling for tenders for the maintenance work to Tumkur Amanikere, Register No. 1 of Tumkur Taluk, in page 273, Part VI of the *Mysore Gazette*, dated 25th February 1937.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 15th March 1937.

An earnest money of Rs. 200 in Treasury Chellan should accompany the tender.

Abstract Notification dated 23rd February 1937.

Attention of the public is drawn to Notification calling for tenders for "restoring breached Kuradihalli Minor Tank, Register No. 23 of Kunigal Taluk," in pages 298-299, Part VI of the *Mysore Gazette*, dated 25th February 1937.

2. Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th March 1937.

3. An earnest money of Rs. 450 in cash should accompany the tender.

Notification dated 8th March 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M., on Monday, the 29th March 1937, for supplying and erecting a Tower Clock on the Tower of the District Office Building at Tumkur, as per specifications given below. The work should be completed within four months from the date of acceptance of tender.

2. The plan, estimate and conditions may be seen at the Office of the Executive Engineer, Tumkur Division, between the hours of 11 A.M. to 5 P.M. on the working days.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer, Tumkur Division, Tumkur.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash, or Government Promissory Notes, as earnest money and be superscribed "tender for supplying and erecting a Tower Clock on the Tower of the District Office Building at Tumkur", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond and also deposit another Rs. 150, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, and also the party intimated officially in due course. No enquiry *re* the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enahanced on any account.

10. Rate for non-tendered and non-estimated items, if any, shall be as per schedule rates of the Department, or those fixed by the Executive Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements and quality of works, etc., and in all disputes of any kind, the decision of the Superintending Engineer, will be final and legally binding.

12. Quotations must be given in words, as well as in figures. Any quotation quoted at so much percentage less or more than the estimated rate, will not be accepted.

13. Tenders received for specifications other than those mentioned below, will not be taken into consideration, but such tenders will be rejected entirely.

Specifications for supplying, erecting and fixing a Tower Clock on the Tower of the District Office Building at Tumkur.

(1) The clock to be of best make, striking only hours, and not half hours.
(2) The wheels to be of gun metal, or bronze except those of winding gear which should be of cast iron.
(3) The pinions to be of steel casting.
(4) Teeth to be cut with mathematical precision.

(5) Escapement to be of Graham Type.

(6) Long, heavy pendulum controlled by an accurate regulator.

(7) The bearings to be of Gun Metal screwed to the frame so as to ensure alignment in a perfect manner.

(8) Counter-sunk, and dust proof oil holes to be provided for perfect lubrication.

(9) The arbors to be of special stainless steel.

(10) All the wheel work to be contained in cast iron frame perfectly planed and true, and rigidly fixed on wooden beams or steel joists in the clock tower.

(11) A type of maintaining power mechanism to prevent the clock from stopping when it is being wound.

(12) The dials to be of metal, three in number fixed on three faces only, and four feet diameter or square, opaque with Roman Figures. The hands, figures and minute divisions to be painted in white and black hard enamel.

(13) Winding to be automatic by Electric current of 220 volts, 25 cycles, and striking only hours, and going a reserve of about 10 hours by providing a dozen cells of 12 Amp. capacity each, which will put into operation automatically in case of failure of the mains.

(14) Steel bell weighing about 5 cwts., will be supplied by this Department, and fixing charges only will be paid to the tenderer of the clock.

(15) An indicating Dial to be provided inside to facilitate setting the Tower Clock.

(16) The clock to be tested for about four months after erection and a reserve of 10 per cent will be withheld in bills, and will be paid back in the final bill.

(17) The clock to be guaranteed to give an almost ever-lasting service.

(18) After the acceptance of the tender the successful tenderer should submit the necessary detailed drawings showing the arrangement of the frame work etc., required for erection of the clock.

(19) All masonry and frame works connected with the erection shall be carried by this Department.

(20) Other minor details required for the clock should be to suit the above specifications.

(21) The inner dimension of the room where the clock is to be located will be approximately about 6 feet long and 6 feet wide.

(22) The approximate height from the ground to the centre of the clock will be about 55 feet.

(23) The quotations to include cost of supplying, fixing and erection, etc., at site.

Description	Rate in figures	Rate in words
Rate for supplying, fixing and erecting a Tower Clock at Tumkur as per specifications given above, complete.		

D. KRISHNA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 24th February 1937.

CONSTRUCTING URDU BOYS' MIDDLE SCHOOL AT SHIMOGA.

The attention of the public is hereby invited to the advertisement in pages 305-307 of the *Mysore Gazette*, dated 4th March 1937, calling for tenders for "Constructing Urdu Boys' Middle School at Shimoga".

Each tender must be accompanied by a Treasury challan for having deposited Rs. 360 as earnest money.

The last date for receiving tenders is 2 P.M. on Friday the 19th March 1937.

P. SUBBA RAO,
Executive Engineer.